


**ADDENDUM 1**

**ADDENDUM DATE:** February 1, 2012  
**PROJECT:** Dobbs School - Vocational Building Upgrades  
**OWNER:** N.C. Department of Juvenile Justice & Delinquency Prevention  
**ARCHITECT:** Smith Sinnett Architecture, P.A.  
4600 Lake Boone Trail, Suite 205  
Raleigh, North Carolina 27607



**Revision and Additions to the Project Manual:**

- Item 1 **REVISION:** Cold Formed Metal Framing, 05 40 00 - Section 1.5.C, Delete the last sentence that states: "All shop drawings and calculations shall be designed and sealed by a professional engineer licensed in North Carolina".
- Item 2 **CLARIFICATION:** General - General Contractor is responsible for all slab cutting and patching.

**Revision and Additions to the Drawings:**

- Item 3 **CLARIFICATION:** 3/A-1 - Keyed Demolition Note 3: General Contractor is to coordinate all slab cutting sizes with subcontractor. Concrete cutting shown is diagrammatic and General Contractor shall cut as required for new installation.
- Item 3 **CLARIFICATION:** 6/A-1 - All penetrations through existing walls will need to be sealed as if they were fire rated penetrations.
- Item 3 **ADDITION:** 6/A-1 - At all slab cut areas, patched back with minimum 4" of stone, vapor barrier as specified, weld wire fabric, and concrete. The new concrete trench shall be tied into the exiting concrete slab by doweling in 16" #4 reinforcing bar at 24" O.C. each side of the trench.

**End of Addendum 1**